

ग्रामीण रुग्णालय, धारुर, पाटोदा व उपजिल्हा रुग्णालय, केज, जि.बीड येथे सोलार वॉटर बसविणे कामाच्या अंदाजपत्रकास प्रशासकीय मान्यता मिळण्याबाबत.

महाराष्ट्र शासन
सार्वजनिक आरोग्य विभाग
शासन निर्णय क्रमांक: प्रशामा-२०२५/ प्र.क्र.२०१/ पासु-२
मंत्रालय, १० वा मजला, संकुल इमारत,
गोकूलदास तेजपाल रुग्णालय आवार, मंत्रालय, मुंबई.
तारीख: ०९ जून, २०२६.

वाचा :-

सहसंचालक, आरोग्य सेवा रुग्णालये (राज्यस्तर), मुंबई यांचे पत्र क्रमांक: आआसे/ कक्ष- ३/टे-६/ धारुरपाटोदावकेजसोलार/१२६४-६५/२५, दिनांक २८.०१.२०२५.

प्रस्तावना :-

ग्रामीण रुग्णालय, धारुर, पाटोदा व उपजिल्हा रुग्णालय, केज, जि.बीड येथे सोलार वॉटर बसविणे कामांचे अंदाजपत्रकास प्रशासकीय मान्यता देण्याची बाब शासनाच्या विचाराधीन होती.

शासन निर्णय :-

ग्रामीण रुग्णालय, धारुर, पाटोदा व उपजिल्हा रुग्णालय, केज, जि.बीड येथे सोलार वॉटर बसविणे कामांचे खालील तक्त्यात नमूद विवरण कामांबाबत यासोबतच्या “परिशिष्ट- अ ते क” मध्ये दर्शविण्यात आल्याप्रमाणे रु. ४,४६,२१७/-, रु.४,४६,२१७/- व रु.१०,४५,३१०/- असे एकूण रु.१९,३७,७४४/- (अक्षरी रुपये एकोणीस लक्ष सदोतीस हजार सातशे चव्वेचाळीस फक्त) इतक्या रकमेच्या ३ अंदाजपत्रकास खालीलप्रमाणे कामनिहाय प्रशासकीय मान्यता देण्यात येत आहे.

अ.क्र.	कामाचे विवरण	अंदाजपत्रक रक्कम (रुपयात)
१	ग्रामीण रुग्णालय, धारुर, जि.बीड येथे सोलार वॉटर बसविणे	रु.०४,४६,२१७/-
२	ग्रामीण रुग्णालय, पाटोदा, जि.बीड येथे सोलार वॉटर बसविणे	रु.०४,४६,२१७/-
३	उपजिल्हा रुग्णालय, केज, जि.बीड येथे सोलार वॉटर बसविणे	रु.१०,४५,३१०/-
	एकूण	रु. १९,३७,७४४/-

२. उपरोक्त अंदाजपत्रकाची प्रशासकीय मान्यता पुढील अटी व शर्तीच्या अधिन राहून देण्यात येत आहे.

अटी व शर्ती :-

- कामासाठी निविदा मागविण्याआधी सदर कामास मुख्य अभियंता, (विदयुत) सार्वजनिक बांधकाम विभाग यांची तांत्रिक मंजूरी घेणे आवश्यक राहिल.

- २) इमारतीचे आराखडे हे सार्वजनिक बांधकाम विभाग/शासकीय इमारतीच्या अनुज्ञेय मानकास अनुसरून असण्याची खातरजमा करावी. अशा नकाशांना व वास्तुमांडणी आराखडयास शासनाचे वास्तुशास्त्रज्ञ यांची मान्यता देण्यात यावी.
- ३) इमारत बांधकाम करण्यापूर्वी विदयुतीकरणाच्या कामासाठी मुख्य अभियंता (विदयुत) व स्थापत्यांच्या कामासाठी मुख्य अभियंता (स्थापत्य) यांची तांत्रिक मंजूर घेण्यात यावी.
- ४) बांधकामासाठी उपलब्ध होणाऱ्या नियतव्ययामधून सदर कामास निधी उपलब्ध करून देण्याच्या अटीच्या अधिन राहून प्रशासकीय मान्यता देण्यात येत आहे.
- ५) कामासाठीच्या जागेची उपलब्धता, योग्यता व जागा पुरेशी आहे किंवा नाही याबाबतची खात्री संबंधित आरोग्य संस्था प्रमुखांनी करावी.
- ६) क्षेत्रिय जागेच्या परिस्थितीनुसार व आरोग्य संस्थांच्या आवश्यकतेनुसार प्रस्तावित कामाच्या किंमतीमध्ये अनावश्यक वाढ करण्यात येऊ नये.
- ७) सदरचे अंदाजपत्रक हे ढोबळ नमुना अंदाजपत्रक असल्याने, या कामांच्या सविस्तर अंदाजपत्रकांना तांत्रिकदृष्ट्या मान्यता ही सार्वजनिक बांधकाम खात्याच्या त्यात्या- क्षेत्राच्या सक्षम अधिकाऱ्यांकडून करण्यात येईल.
- ८) स्थानिक ग्रामीण नगर विकास संस्थेच्या संबंधित नियमानुसार बांधकाम परवानगी तसेच भोगवटा प्रमाणपत्र मिळविण्याची जबाबदारी सार्वजनिक बांधकाम विभाग यांची राहिल.
- ९) शासनाच्या प्रचलित नियमानुसार निविदा प्रक्रिया राबविण्यात यावी.
- १०) प्रत्यक्ष काम करतेवेळी पर्यावरण विभाग, शासन निर्णय क्र.इएनव्ही-२०१३/प्र.क्र.१७७/तां.क.१ दि. १० जानेवारी, २०१४ मध्ये उल्लेख करण्यात आलेल्या मार्गदर्शक तत्वांनुसार कार्यवाही करण्यात यावी.
- ११) रुग्णालयाचे नकाशे तपासून नकाशांमध्ये रुग्णालयासाठी आवश्यक ऑक्सिजन पाईपलाईन, एअर कंडीशनरसाठी जागा व त्यांच्या duct चे नियोजन, दिव्यांगांकरीता करावयाच्या सोयीसुविधा, त्या व्यक्तींसाठी रुग्णालयात करावयाचे पथ-वे इ. तसेच याबाबतची Functionality विचारात घेवून रुग्णालयाचे नकाशे सुधारीत करण्यात यावेत. तसेच रुग्णालय डिझायनिंग मधील तज्ञ व्यक्ती व रुग्णालयाशी संबंधित डॉक्टर व कर्मचारी यांचेशी चर्चा करून त्यानुसार रुग्णालयाचे नकाशे सुधारित करण्यात यावेत.
- १२) केंद्र शासनाकडून निर्गमित IPHS च्या २०२२ च्या मार्गदर्शक सुनचांनुसार अंदाजपत्रकामध्ये सुधारणा समाविष्ट करून प्रशासकीय मान्यतेच्या किंमतीच्या मर्यादेत राहून इमारतीचे बांधकाम करण्यात यावे.
- १३) प्रस्तावित करण्यात आलेल्या इमारतीचे जोते क्षेत्रफळ व शासकीय इमारती यांच्या अनुज्ञेय मानकाप्रमाणे असल्याची खातरजमा करण्यात यावी.

१४) सार्वजनिक बांधकाम विभाग, शासन निर्णय क्र.बीडीजी२०१७/प्र.क्र.६०/इमा-२, दि.०७.०७.२०१७ अन्वये कार्यवाही करावी.

१५) नियोजित जागा उपभोक्ता विभागाच्या ताब्यात असल्याचे प्रमाणपत्र प्राप्त करूनच सदर कामाच्या निविदा सुचना प्रसिध्द करण्यात याव्यात.

३. सदर कामावरील खर्च मागणी क्रमांक- एच-८, “मुख्य लेखाशिर्ष - ४२१० - वैद्यकीय सेवा व सार्वजनिक आरोग्य यावरील भांडवली खर्च, ०२- ग्रामीण आरोग्य सेवा (वैद्यकीय सहाय), ११०- रुग्णालये व दवाखाने, ०४-सार्वजनिक आरोग्य, १०४-सामुहिक आरोग्य केंद्र, (००) (०१)- मोठी बांधकामे (४२१० ०३९१), ५३ - मोठी बांधकामे” या लेखाशिर्षामधून भागविण्यात येईल.

४. सदर शासन निर्णय, शासन निर्णय, वित्त विभाग क्रमांक.विअप्र-२०१३/प्र.क्र.३०/२०१३/विनियम, भाग-२, दिनांक १७ एप्रिल, २०१५ व दिनांक २० सप्टेंबर, २०१९ सोबतच्या परिशिष्ट भाग-पहिला, उपविभाग- पाच मधील अनुक्रमांक १, परिच्छेद क्र.१३४ (१) नुसार प्रशासकीय विभागांना प्रदान करण्यात आलेल्या अधिकारात निर्गमित करण्यात येत आहे.

५. सदर शासन निर्णय महाराष्ट्र शासनाच्या www.maharashtra.gov.in या संकेतस्थळावर उपलब्ध करण्यात आला असून त्याचा संकेतांक २०२६०६०९१२२१३४५७१७ असा आहे. हा आदेश डिजीटल स्वाक्षरीने साक्षांकित करून काढण्यात येत आहे.

महाराष्ट्राचे राज्यपाल यांच्या आदेशानुसार व नावाने,

KAVITA

PRADIP PISE

Digitally signed by KAVITA
PRADIP PISE
DN: cn=KAVITA PRADIP PISE, o,
ou, email=kavita.pise@nic.in,
c=US
Date: 2026.06.09 12:55:39 +05'30'

(कविता पिसे)

अवर सचिव, महाराष्ट्र शासन

प्रत,

- १) महालेखापाल (लेखा व लेखापरिक्षा/लेखा व अनुज्ञेयता), महाराष्ट्र-१/२, मुंबई/ नागपूर.
- २) आयुक्त, आरोग्य सेवा तथा अभियान संचालक, राष्ट्रीय आरोग्य अभियान, मुंबई.
- ३) सहसंचालक, आरोग्य सेवा (अर्थ व प्रशासन), पुणे.
- ४) उपसंचालक, आरोग्य सेवा, लातूर मंडळ, लातूर.
- ५) सहाय्यक संचालक (लेखा व लेखापरिक्षा), आरोग्य सेवा, पुणे.
- ६) जिल्हा शल्य चिकित्सक, जिल्हा रुग्णालय, बीड.
- ७) जिल्हा कोषागार अधिकारी, बीड.
- ८) मुख्य अभियंता, सार्वजनिक बांधकाम मंडळ (विद्युत), मुंबई.

- ९) मुख्य अभियंता, सार्वजनिक बांधकाम मंडळ (विद्युत), मुंबई
- १०) अधीक्षक अभियंता, सार्वजनिक बांधकाम विभाग (विद्युत), नांदेड.
- ११) कार्यकारी अभियंता, सार्वजनिक बांधकाम विभाग (विद्युत), धाराशिव.
- १२) निवडनस्ती (आरोग्य-४).

ABSTRACT -SHEET PART A

Name of work

Est.no:OW/5266/2022-23 Providing Solar Water Heater at Subdistrict Hospital At DharurTq Dharur Dist Beed

Sr.No	Qty	Item no	Description	Unit	Rate	Amount.
1	10	3-1-7	Supplying and erecting chromium plated heavy duty brass stop cock for inlet pipe of water heater (15mm. dia).	Each	246.75	2467.50
2	2	4-1-4	Supplying, installing, testing and commissioning of FPC solar water heating system without heat exchanger type of 500 LPD capacity with SS water tank of 0.5 mm thickness conforming to IS1239 Part-I :2004 complete as per specification no. ESD-SHWS-FPC	Each	95167.80	190335.60
3	60	4-2-18 (New)	Supplying and erecting 20/25 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 2.6 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	222.60	13356.00
4	50	4-2-19 (New)	Supplying and erecting 25/32 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 3.2 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	355.95	17797.50
5	2000	4-8-7	Providing and fixing high-density polyethylene (HDPE) container one piece moulded triple layer water tank made out of high density polyethylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all	per litre	10.50	21000.00
6	490.6	6-1-19	Supplying and erecting iron work, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials duly painted with one coat of red oxide and two coats of enamel paint to match the switchgears or as per directions by the authority.	kg	195.30	95814.18
7	1.5	16-3-7	Making cement concrete foundation in 1:3:6 cement concrete, (20 to 25) mm. stone metal duly plastered with necessary curing for complete. (pole muffing or any other purpose).	m ³	3606.75	5410.13
8	15	16-5-3	Supplying and erecting ISI mark GI pipe 25 mm. dia. 'B' class at position with accessories complete as per specification no. CW-PLB/GP.	m	355.95	5339.25
9	10	16-6-13	Supplying and erecting 25 mm dia. gun metal sluice valve at position with necessary materials complete.	Each	916.65	9166.50
10	5	16-6-19	Supplying and erecting non return valve 25 mm dia in position made of gun metal complete.	Each	583.80	2919.00
A Total						363605.66
B add 4% Contengency on A						14544.23
C Total A+B						378149.88
D Add 18% GST on C						68066.98
E Total on C+D						446216.86
F Say E						446217.00

Recommended for T.A.

Superintending Engineer
Nanded PWD Electrical Region
NANDED.

P.W.D.(Elect) Supervisor
Beed

Deputy Engineer

Beed

TECHNICALLY APPROVED

Executive Engineer

P.W.D.(Electrical) Division
Osmanabad

For Rs. 4,46,217/-

Chief Engineer (Elect.),
Public Works Department,
Mumbai - 400 001.

"Subject to Conditions Mentioned in
Letter No. 291/.....Dt. 09/02/23"

" ५१२१२ - ४ "

ABSTRACT -SHEET PART A

Name of work:

Est.no:OW/5265/2022-23Providing Solar Water Heater at Subdistrict Hospital At Patoda
Tq Patoda Dist Beed

Sr.No	Qty	Item no	Description	Unit	Rate	Amount.
1	10	3-1-7	Supplying and erecting chromium plated heavy duty brass stop cock for inlet pipe of water heater (15mm. dia).	Each	246.75	2467.50
2	2	4-1-4	Supplying, installing, testing and commissioning of FPC solar water heating system without heat exchanger type of 500 LPD capacity with SS water tank of 0.5 mm thickness conforming to IS1239 Part-I :2004 complete as per specification no. ESD-SHWS-FPC	Each	95167.80	190335.60
3	60	4-2-18 (New)	Supplying and erecting 20/25 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 2.6 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	222.60	13356.00
4	50	4-2-19 (New)	Supplying and erecting 25/32 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 3.2 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	355.95	17797.50
5	2000	4-8-7	Providing and fixing high-density polyethylene (HDPE) container one piece moulded triple layer water tank made out of high density polyethylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all	per litre	10.50	21000.00
6	490.6	6-1-19	Supplying and erecting iron work, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting, drilling and welding complete erected at the position with necessary materials duly painted with one coat of red oxide and two coats of enamel paint to match the switchgears or as per directions by the authority.	kg	195.30	95814.18
7	1.5	16-3-7	Making cement concrete foundation in 1:3:6 cement concrete, (20 to 25) mm. stone metal duly plastered with necessary curing for complete. (pole mufing or any other purpose).	m ³	3606.75	5410.13
8	15	16-5-3	Supplying and erecting ISI mark GI pipe 25 mm. dia. 'B' class at position with accessories complete as per specification no. CW-PLB/GP.	m	355.95	5339.25
9	10	16-6-13	Supplying and erecting 25 mm dia. gun metal sluice valve at position with necessary materials complete.	Each	916.65	9166.50
10	5	16-6-19	Supplying and erecting non return valve 25 mm dia in position made of gun metal complete.	Each	583.80	2919.00
A Total						363605.66
B add 4% Contengency on A						14544.23
C Total A+B						378149.88
D Add 12% GST on C						68066.98
E Total on C+D						446216.86
F Say E						446217.00

Recommended for T.A.

Superintending Engineer
Nanded PWD Electrical Region
NANDED.

Deputy Engineer
P.W.D.(Elect) Sub Division
Beed

TECHNICALLY APPROVED

For ₹4,46,217/-

Executive Engineer
D.(Electrical) Division
Osmanabad

Chief Engineer (Elect.),
Public Works Department,
Beed


"Subject to Conditions Mentioned in
Letter No. 291.....Dt. 09/02/2023
Page 1


ABSTRACT -SHEET PART A

Name of work

Est.no:OW/5262/2022-23 Providing Solar Water Heater at Subdistrict Hospital At KaijTq Kaij Dist Beed

Sr.No	Qty	Item no	Description	Unit	Rate	Amount.
1	20	3-1-7	Supplying and erecting chromium plated heavy duty brass stop cock for inlet pipe of water heater (15mm. dia).	Each	246.75	4935.00
2	5	4-1-4	Supplying, installing, testing and commissioning of FPC solar water heating system without heat exchanger type of 500 LPD capacity with SS water tank of 0.5 mm thickness conforming to IS1239 Part-I :2004 complete as per specification no. ESD-SHWS-FPC.	Each	95167.80	475839.00
3	100	4-2-18 (New)	Supplying and erecting 20/25 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 2.6 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	222.60	22260.00
4	80	4-2-19 (New)	Supplying and erecting 25/32 mm (ID/OD) Chlorinated polyvinyl chloride pipe (CPVC), thickness 3.2 mm conforming to IS 15778 (CTS Series) with necessary CPVC fittings and solvent cement for Solar Water Heater System as per specification No. ESD-HWP/CPVC	m	355.95	28476.00
5	5000	4-8-7	Providing and fixing high-density polyethylene (HDPE) container one piece moulded triple layer water tank made out of high density polyethylene and built corrugated inclusive of delivery up to destination hoisting and fixing of accessories such as inlet, outlet overflow pipe inclusive of all	per litre	10.50	52500.00
6	1226.5	6-1-19	Supplying and erecting iron work, sheet metal work consisting of CRCA sheets, various sections of iron, plates, chequered plates, rods, bars, MS pipes, etc. for panel board or any other purpose with bending, cutting,	kg	195.30	239535.45
7	3	16-3-7	Making cement concrete foundation in 1:3:6 cement concrete, (20 to 25) mm. stone metal duly plastered with necessary curing for complete. (pole muffing or any other purpose).	m ³	3606.75	10820.25
8	15	16-5-3	Supplying and erecting ISI mark GI pipe 25 mm. dia. 'B' class at position with accessories complete as per specification no. CW-PLB/GP.	m	355.95	5339.25
9	10	16-6-13	Supplying and erecting 25 mm dia. gun metal sluice valve at position with necessary materials complete.	Each	916.65	9166.50
10	5	16-6-19	Supplying and erecting non return valve 25 mm dia in position made of gun metal complete.	Each	583.80	2919.00
A Total						851790.45
B add 4% Contengency on A						34071.62
C Total A+B						885862.07
D Add 18% GST on C						159355.17
E Total on C+D						1045317.24
F Say E						1045317.24


Deputy Engineer
P.W.D.(Elect) Sub-Division
Beed


Executive Engineer
P.W.D.(Electrical) Division
Osmanabad

Recommended for T.A.


Superintending Engineer
Nanded PWD Electrical Region
NANDED.

TECHNICALLY APPROVED

For ₹10,45,317/-


Chief Engineer (Elect.),
Water Works Department,
Mumbai - 400 001.

"Subject to Conditions Mentioned in
Letter No. 291.....Dt. 09/02/23"